

West Pinal PM10 Nonattainment Area Construction Dust

Dust Generating Standards

All work sites 0.1 acre or more will comply with the following:

1. 20% opacity standard for any dust generating operation that occurs during construction
2. Stabilizing construction area. Every other week inspections are to be conducted to ensure the entire work site is stabilized using all control measures as listed in the permit.

All work sites or a combination of work sites where activities will disturb 5 acres or more will comply with the following:

1. Installation of a trackout control device prior to starting dust generating operation.
2. For areas where the dust generating operation has ceased or will cease for more than 30 days, will install signs or physical barriers to limit trespassing.
3. Inspect the complete site the day leading up to and the day of a high risk for dust emissions (Pinal County Dust Risk Forecast) to ensure the work site is stabilized and all control measures that apply to the work site are implemented and the disturbed surface areas are stabilized. Complete either of the following:
 - a. All dust generating operations are ceased and disturbed surface areas are stabilized.
 - b. Maintain documentation that dust generating operations still being performed are not causing or contributing to an opacity violation. Such documentation could include opacity observations by a certified observer.